

KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)

NOTICE INVITING RE-QUOTATION

PLD-E/E5/7966/2021

29.06.2024

Sealed competitive Re-quotations for "**Maintenance works at Ladies Hostel, Nileswaram Campus of Kannur University**" are invited from registered/Authorized competent Contractors/firms. The name of work shall be super scribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 12-7-24 at 3.00 pm and the Quotations will be opened at 3.30 pm on the same day.

Conditions:-

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Registrar on recommendations of the Engineer in Charge and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. Work shall be completed within 6 months from the date of agreement.
5. The Defect Liability Period shall be 18 months from the date of completion of work (as reported by the University EE) and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge .
6. Successful Quotationer shall deposit a sum equivalent to 5% of the value of contract as performance Guarantee within the period specified in the work order.
7. The contractor shall make his own arrangements for electricity and water.
8. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
9. Quotation schedule is appended

For more details, contact the Engineering wing, Kannur University, Thavakkara, Kannur-2. (Ph.No: 04972715257, 04972715251)

The Registrar, Kannur University reserves the right to reject any of the Quotation or all the Quotations without assigning any reason whatsoever.


Registrar

J.

KANNUR UNIVERSITY						
QUOTATION SCHEDULE						
Name Of Work: MAINTENANCE WORK OF LADIES HOSTEL AT NILESWARAM CAMPUS						
SL. NO	QTY	PARTICULARS	UNIT	RATE INCLUDING ALL TAXES		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1	30	15.23.1 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm			
2	30	11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600 x 600 mm.	Sqm			
3	1	17.69.2 Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour. Waste coupling 38 mm dia of 83 mm length and 77 mm breadth, weighing not less than 60 gms	nos			
4	3	50.18.9.7.1 Providing and fixing PVC pipes including of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge. 63 mm dia 6Kgf/cm ²	metre			
5	3	50.18.9.17.1 Providing and fixing PVC pipes including fixing the pipe with clamps/ clip at 1.00 m spacing . This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 6 Kgf/cm ² - External work - Exposed on wall	metre			
6	2	50.18.9.20.1 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 63 mm dia Elbow	nos			
7	2	50.18.9.20.9 Providing and fixing PVC moulded fitting / accessories for Rigid PVC pipes, including jointing with PVC solvent cement-63 mm dia Socket /coupling	nos			
8	5	50.18.9.14.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kgf/cm ² - External work- Exposed on wall	metre			
9	1	Disposal work of wastes in waste bin	unit			
TOTAL						
(Rupees.....Only)						
Signature:						
Name & Address of the Quotationer:						
Date:						

Last date of Receipt: 12/07/24,
3 PM