

(PLANNING AND DEVELOPMENT BRANCH)

PLD-D/D-2/23488/2023

21.04.2025

QUOTATION NOTICE

Sealed competitive Quotations are invited from Registered/Authorized firms for the following works of Kannur University:

1. Maintenance works for Economics building at Palayad campus
2. Maintenance works for Ladies Hostel rest room at Palayad Campus

The Quotations with all details should reach the office of the Registrar, Kannur University, Thavakkara Campus on 06.05.2025 by 3:00 pm and will be opened on the same day at 3:30 pm.

Conditions:

1. The rate quoted should be **inclusive of GST and all other charges if any**. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Executive Engineer and work shall be executed as per KPWD specifications.
3. The Payment will be made through bank account and no advance payment will be sanctioned.
4. The successful bidder will be required to deposit Performance Guarantee/Security Deposit of 5% of APAC .
5. Work shall be completed within **2 (TWO) Months** from the date of executing the agreement.
6. A defect liability period is **6 (SIX) Months** from the date of completion of work
7. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
8. The Registrar, Kannur University reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.
9. Quotation schedule is appended herewith.

For more details, contact the Engineering wing, Kannur University, Thavakkara, Kannur-2. (Ph.No: 0497-2715390)


Registrar

Notice Board/ Website

Engineering wing (for maximum publicity and information to PWD office and Dist. Information Office, Kannur) / PRO

| KANNUR UNIVERSITY | | | | | | | |
|--|---|--|--------------------------|-----------------|---------------|--------|---------|
| QUOTATION SCHEDULE | | | | | | | |
| NAME OF THE WORK: Maintenance works for Economics building , Maintenance works for Hostel rest room at Palayad Campus. | | | | | | | |
| | | | LAST DATE OF SUBMISSION: | | | | |
| SL NO | QUANTITY | ITEM DESCRIPTION | UNIT | RATE IN FIGURES | RATE IN WORDS | AMOUNT | REMARKS |
| (a) | Maintenance work for Economics building | | | | | | |
| 1 | 1 | 14.82 Dismantling W.C. Pan of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in-Charge | nos | | | | |
| 2 | 1.44 | 15.23.2 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. | sqm | | | | |
| 3 | 1.44 | 11.41.1 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm | sqm | | | | |
| 4 | 1 | 17.2.2 Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: W.C. pan with ISI marked black solid plastic seat and lid | each | | | | |

| | | | | | | | |
|----|----|--|-------|--|--|--|---|
| 5 | 1 | Supplying and fixing CP Health Faucet superior quality (Jagur or equivalent make) including cost of materials and labour charges etc complete as per the direction of site Engineer-in-charge. | nos | | | | |
| 6 | 12 | 50.18.9.9.1 Providing and fixing PVC pipes includings jointing of pipes with one step PVC solvent cement, trenching, refilling & testing of Joints complete as per direction of engineer in charge.110 mm dia 6Kgf/cm2 | metre | | | | |
| 7 | 3 | 50.18.9.8.2 Providing and fixing PVC pipes includings of pipes with one step PVC solvent cement, trenching and refilling & testing of joints complete as per direction of Engineer in Charge. 75 mm dia 4 Kgf/cm2 | metre | | | | " |
| 8 | 3 | 18.53.1 Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS: 8931 15 mm nominal bore | each | | | | |
| 9 | 2 | 50.18.9.22.2 Providing and fixing PVC moulded fittings / accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110 mm dia 45 degree Elbow | nos | | | | |
| 10 | 1 | 50.18.9.22.6 Providing and fixing PVC moulded fittings/accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 110x110x110 mm dia Door tee | nos | | | | |
| 11 | 1 | 50.18.9.22.11 Providing and fixing PVC moulded fittings/accessories for Rigid PVC pipes,including jointing with PVC solvent cement - 110 mm dia Socket/ coupling | nos | | | | |
| 12 | 2 | 18.51.1 Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. | each | | | | |
| 13 | 1 | 50.18.9.21.9 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 75 mm dia Socket /coupling | nos | | | | |

| | | | | | | | |
|------------|--|--|------|--|--|--|--|
| 14 | 1 | 50.18.9.21.7 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 75 mm dia Vent cowl | nos | | | | |
| 15 | 3 | 50.14.1.1 Removing and refixing door shutters after necessary repairs for easy opening and closing etc complete as per the direction of site Engineer-in-charge. | each | | | | |
| 16 | 14 | 50.14.1.2 Removing and refixing window shutters after necessary repairs for easy opening and closing etc complete as per the direction of site Engineer-in-charge | each | | | | |
| (b) | Maintenance works of rest room at ladies Hostel | | | | | | |
| 1 | 4 | 15.13.1 Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead:Of area 3 sq. metres and below | each | | | | |
| 2 | 0.152 | 15.14.1 Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead: Of sectional area 40 square centimetres and above | cum | | | | |
| 3 | 0.05 | 9.1.1 Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).Second class teak wood | cum | | | | |
| 4 | 3.78 | 50.9.3.1 Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows, 30 mm thick shutters including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding paneling which will be paid for separately, all complete as per direction Of Engineer in- charge. using Anjili/ Jack wood | sqm | | | | |
| 5 | 4.312 | 9.48.1 Providing and fixing M.S. Grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.Fixed to steel windows by welding | kg | | | | |

| | | | | | | | |
|---|--------|---|-----|--|--|--|--|
| 6 | 12.483 | providing and fixing metal net for openings including all materials and labour charges etc complete | sqm | | | | |
| | | (Including GST) TOTAL AMOUNT | | | | | |
| | | Rupees..... | | | | | |

SIGNATURE

NAME & ADDRESS OF THE CONTRACTOR



REGISTRAR

~