

**KANNUR UNIVERSITY**  
(Planning and Development Branch)  
NOTICE INVITING QUOTATIONS

PLD/E-4/22440/2025

27.11.2025

Sealed competitive Quotations Super scribed as "UPS Wiring work at Cherussery Auditorium, Thavakkara Campus" are invited from registered competent Contractors/firms.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 27/12/2025 at 3 pm and the quotations will be opened at 3.30 pm on the same day .

Conditions:

1. The rate quoted should be exclusive of GST and all other charges if any. GST charges and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted
2. The contractor shall arrange all materials & equipment and should be got approved by the Registrar on recommendations of the Engineer in charge and work shall be executed as per KPWD specifications.
3. The Payment will be made through the bank account, and no advance payment will be sanctioned
4. Work shall be completed within 30 days from the date of the Agreement.
5. The Engineer in Charge shall be AE Electrical Kannur University.
6. The defect Liability period shall be 18 months from the date of completion of the work. and the contractor shall be responsible to maintain all his works till completion.
7. The successful Quotationer shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit within the period specified in the Work order
8. The quotationer, before submitting the quotation for the work, shall ensure that, the quotationer visited the Site and satisfied himself about the site conditions for the works (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen, and materials as well as permission from Authorities for this purpose
9. The Contractor shall make his own arrangements of Water and Electricity.
10. Quotation forms and details of works can be had from the [www.kannuruniv.ac.in](http://www.kannuruniv.ac.in).
11. Quotation Schedule is appended.

The Registrar, Kannur University, reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



  
Registrar



## KANNUR UNIVERSITY

## Quotation shedule for UPS Wiring Work at Cherussery Auditorium,Thavakkara Campus

LAST DATE OF SUBMISSION:

| SL. NO | ITEM DESCRIPTION                                                                                                                                                                                                                                             | UNIT | QTY | RATE IN FIGURES | RATE IN WORDS | AMOUNT | REMARKS |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-----|-----------------|---------------|--------|---------|
| 1      | Supplying and drawing following sizes offRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 2.5 sq. mm                                                                              | Mtr  | 20  |                 |               |        |         |
| 2      | Supply and laying medium gauge pvc conduit of the following sizes conforming to IS 9537/1983 Part III in roofslab jointing the pipes with forcement PVC solvent cement, tying & amp fixing the conduit firmly with the re-inforcement etc. as required.20 mm | Mtr  | 10  |                 |               |        |         |
| 3      | Supplying and drawing following sizes offRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 X1.5sq.mm                                                                                 | Mtr  | 30  |                 |               |        |         |
| 4      | Supplying and drawing following sizes offRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x6sq.mm                                                                                   | Mtr  | 10  |                 |               |        |         |
| 5      | Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.63 amps                                                                                 | Each | 1   |                 |               |        |         |



|   |                                                                                                                                                                                                                                                                                                                                      |             |   |  |  |  |  |  |            |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|---|--|--|--|--|--|------------|
| 6 | Supplying and fixing following rating, double pole, (single phase and neutral), 240 volts, residual current circuit breaker (RCCB), having a sensitivity current 30 milli amperes in the existing MCB DB complete with connections, testing and commissioning etc. as required. 63amps                                               | Each        | 1 |  |  |  |  |  |            |
| 7 | Supplying and fixing 5.A. to 32 A rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole                                                                        | Each        | 5 |  |  |  |  |  |            |
| 8 | Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/isolator) 12 way, Double door | Each        | 1 |  |  |  |  |  |            |
|   |                                                                                                                                                                                                                                                                                                                                      | Total       |   |  |  |  |  |  |            |
|   |                                                                                                                                                                                                                                                                                                                                      | 18% GST     |   |  |  |  |  |  |            |
|   |                                                                                                                                                                                                                                                                                                                                      | Grand total |   |  |  |  |  |  | .....Only) |
|   |                                                                                                                                                                                                                                                                                                                                      | (Rupees     |   |  |  |  |  |  |            |

SIGNATURE

Name &amp; Address of the of the Contractor

Date

REGISTRAR

