

PLD-E/E5/6961/2026

Date:23.06.2026

Reference: Quotation Notice No. PLD-E/E5/6961/2026 dated 08.06.2026

Quotation for "UPS Wiring work at Palayad Campus-" -Last date of receiving of quotation - extended -reg.

The Last date for receiving of quotation for "UPS Wiring work at Palayad Campus " is extended till 01.07.2026 at 3 PM .Time of opening -3.30 PM

sd/-
REGISTRAR





KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING QUOTATION

PLD-E/E5/6961/2026

08.06.2026

Sealed competitive Quotations for "**UPS Wiring work at Palayad Campus-UPS wiring** " are invited from registered competent Electrical contractors/ firms. The name of the work shall be superscribed on the cover.

Quotations with all details should reach the office of the Registrar, Kannur University, Kannur-02 on or before 23/6/2026 at 3 pm and the Quotations will be opened at 3:30 p.m. on the same day.

Conditions:

1. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges, and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted.
2. The Contractor shall arrange suitable materials and equipment and should be got approved by the Registrar on recommendations of the Engineer in Charge and work shall be executed as per KPWD specifications. Assistant Executive Engineer(Civil), Kannur University shall be the Engineer-in-charge.
3. The Contractor shall ensure that before submitting quotation for the work, the Contractor visits the site and satisfies himself about the site conditions for constructions and for logistics and smooth flow of workmen and materials as well as permission from the Authorities for this purpose.
4. The Payment will be made through bank account and no advance payment will be sanctioned.
5. Work shall be completed within 30 days from the date of agreement.
6. The Defect Liability Period shall be 1 year from the date of completion of work, and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge .
7. Successful Quotationer shall deposit a sum equivalent to 5 % of the value of the contract as a performance Guarantee within the period specified in the work order.
8. Quotation forms and details of works can be had from the www.kannuruniv.ac.in.
9. Quotation schedule is appended.

The Registrar, Kannur University, reserves the right to reject any of the quotations or all the quotations without assigning any reason whatsoever.



sdl
Registrar

**KANNUR UNIVERSITY
QUOTATION SCHEDULE**

NAME OF THE WORK: UPS WIRING WORK AT PALAYAD CAMPUS (Campus Director office)

LAST DATE OF SUBMISSION:

SL NO	ITEM DESCRIPTION	UNIT	QUANTITY	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x 4 sq. mm	Mtr	90				
2	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.20 mm	Mtr	135				
3	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) 6 way, Double door	Nos	1				
4	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.6 pin 15/16 amp socket outlet	Nos	1				
5	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.5/6 amps switch	Nos	8				
6	Supplying and fixing following piano type switch / socket on the existing switch box/ cover including connections etc. as required.15/16 amp switch	Nos	1				
7	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)6 module moulded plastic box on surface	Nos	3				
8	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x2.5 sq. Mm	Mtr	90				
9	Supplying and fixing metal box of following sizes (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including painting etc as required.75 mm X 75 mm X 60 mm deep	Nos	1				
10	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)2 module moulded plastic box on surface	Nos	1				
11	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)3 module moulded plastic box on surface	Nos	1				

SL NO	ITEM DESCRIPTION	UNIT	QUANTITY	RATE INCLUDING ALL TAXES		AMOUNT	REMARKS
				RATE IN FIGURES	RATE IN WORDS		
12	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.6 Module	Nos	3				
13	Supplying and fixing following rating, double pole, 240 volts, isolator in the existing MCB DB complete with connections, testing and commissioning etc. as required.40 amps	Nos	2				
14	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required. Single pole	Nos	4				
15	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.3 Module	Nos	2				
16	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc. as required.1 or 2 Module	Nos	1				
	Total Amount						
	GST 18%						
	Grand Total						

(RupeesOnly)

SIGNATURE

Name & Address of the of the Contractor

Date